

Riverside Drive Resurfacing

East Hartford, CT



Above: Before and After. Zuvic Carr coordinated the project design with Goodwin College, local utility companies, the Town of East Hartford, and others.

Client

Goodwin College

Completed

2010

Description

Zuvic Carr completed the design and construction administration for approximately 1,800 linear feet of public roadway rehabilitation, including the oversight of traffic counts and a detailed pavement condition investigation. Contract documents were prepared by Zuvic Carr, and we coordinated a pre-build meeting and provided part-time construction inspection services for this project.

Work included shimming and leveling the existing pavement surface, replacing curbing, adjusting utility structures, and installing a new overlay course of Superpave Level 2 hot mix asphalt.